BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/RD/WORK_INDENT11504

APPROVED SCHEDULE - B

Tender Notification EE/BTP/BBMP/E-PMT/18/2013-14, Date: 13.01.2014

Construction of Burial Ground Compound Wall (Balance Work) at Sampigehalli in Ward No.05, in Chokanahalli Village Limits

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S K KESHAVAMURTHY	
				In Figures	In Words
1	299.7	KSRRB 300-1. Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 152/ Item No. 19.2/ PWD SR 2013-14	cum	89.77	Rupees Eighty Nine and Seventy Seven Paise Only
2	49.95	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2013-14	Cum	4245.79	Rupees Four Thousand Two Hundred Forty Five and Seventy Nine Paise Only
3	208.13	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 25/ Item No. 5.6/ PWD SR 2013-14	cum	3512.69	Rupees Three Thousand Five Hundred Twelve and Sixty Nine Paise Only
4	99.9	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 26/ Item No. 5.9/ PWD SR 2013-14	Sqm	4182.74	Rupees Four Thousand One Hundred Eighty Two and Seventy Four Paise Only
5	29.6	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix M10 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2013-14	cum	4688.21	Rupees Four Thousand Six Hundred Eighty Eight and Twenty One Paise Only
6	666	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 27/ Item No. 5.27/ PWD SR 2011-12	Sqm	914.77	Rupees Nine Hundred Fourteen and Seventy Seven Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka, B.B.M.P.

7	333	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 122/ Item No. 15.1/ PWD SR 2013-14	Sqm	79.08	Rupees Seventy Nine and Eight Paise Only
8	240	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 170/ Item No. 20.18/ PWD SR 2013-14	Cum	1109.27	Rupees One Thousand One Hundred Nine and Twenty Seven Paise Only
9	1200	KSRRB 500-4: providing and applying primer coat from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specificationsDo- Medium Porosity MORTH chapter 5, No. 175/ Item No. 21.4/ PWD SR 2013-14	Sqm	99.54	Rupees Ninety Nine and Fifty Four Paise Only
10	30	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. P. No. 174/ Item No. 21.20/ PWD SR 2013-14	Cum	9530.31	Rupees Nine Thousand Five Hundred Thirty and Thirty One Paise Only
11	2.5	Providing and laying reinforced cement concrete pipe NP3 for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials, labour, curing complete as per specifications, specification No. KSRB 1000, 2300 MOST specification1000/2300, 1200mm dia, , No. 257 Item No. 34.6.6 PWD SR 2011-12	Mtrs	8991.71	Rupees Eight Thousand Nine Hundred Ninety One and Seventy One Paise Only
12	1.69	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2013-14	Cum	225.49	Rupees Two Hundred Twenty Five and Forty Nine Paise Only
13	2.05	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2012-13 7	Cum	4245.79	Rupees Four Thousand Two Hundred Forty Five and Seventy Nine Paise Only

Executive Engineer
Byatarayanapura Division
Yalahanka Zone, B.B.M.P.
Bangalore-560092

14	1.35	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 25/ Item No. 5.6/ PWD SR 2013-14	cum	3512.69	Rupees Three Thousand Five Hundred Twelve and Sixty Nine Paise Only
15	1.35	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 26/ Item No. 5.9/ PWD SR 2013-14	Cum	4182.74	Rupees Four Thousand One Hundred Eighty Two and Seventy Four Paise Only
16	2.05	KSRB-4-1.6 : Providing and laying in position plain cement concrete of mix M15 withOPC cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/ P.No. 12/ Item No. 4.6/ PWD SR 2013-14	Cum	4728.82	Rupees Four Thousand Seven Hundred Twenty Eight and Eighty Two Paise Only
17	3.6	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 122/ Item No. 15.1/ PWD SR 2013-14	Sqm	79.08	Rupees Seventy Nine and Eight Paise Only
18	30	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165mm repectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc, complete. Page No. 28/ Item No. 5.30/ PWD SR 2013-14	No.	265.03	Rupees Two Hundred Sixty Five and Three Paise Only
19	13.5	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2013-14	Cum	225.49	Rupees Two Hundred Twenty Five and Forty Nine Paise Only
20	30	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., 75 MM Dia Page No.14 item No.3.4.2 b PRED SR 2010-11.	Rmtr	154.96	Rupees One Hundred Fifty Four and Ninety Six Paise Only
21	13.5	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour complete as per specifications, No. 6/ Item No. 2.11/ PWD SR 2013-14	Cum	58.74	Rupees Fifty Eight and Seventy Four Paise Only
22	6	Elbow, Page No. XXXV PWD SR-2013-14	No	110.63	Rupees One Hundred
23	6	Tee Page No. XXXV PWD SR-2013-14	No	167.23	Rupees One Hundred
24	2	Union Page No. XXXV PWD SR-2013-14	No	221.35	Rupees Two Hundred
25	6	Nipple Page No. XXXV PWD SR-2013-14	No	103.2	Rupees One Hundred

Executive Engineer
Byatarayanapura Division
Yalahanka Zone, B.B.M.P.
Bangalore-560092

26	2	KSRB 13-6.3-6: Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6 / 13.3,Page No. 97/ Item No. 13.37 / PWD SR 2011-12	Each	1477.32	Rupees One Thousand Four Hundred Seventy Seven and Thirty Two Paise Only
27	1	Labour Charges for giving 50mm dia G.I Pipe end connection from rising main to cistern including cutting thereasding conceying laying an d jointing etc, complete inclusive of fixing 4 Nos. of 20mm dia G.I Pipess with taps to the cistern PRED SR-12-13 (P No. 19 I No. 3.13)	Each	1367.18	Rupees One Thousand Three Hundred Sixty Seven and Eighteen Paise Only
28	1	Errection of RCC Hume pipe pump house/Cistern on size stone masory platform including trasportation charges and handing with all necessary tools and plants complete as directed by the Engineer in charge of work. PRED SR 2012-13 (p No. 20 I No. 3.17)	Each	1201.7	Rupees One Thousand Two Hundred One and Seventy Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92